Royalty Statement for the work of: Construction of Headroom, Overhead tank providing Sanitary water supply connections and Electrical works to Marriage Community hall building at Chikkabettahalli in ward No.03

Sl.No	Particulars	Unit	Quantity	Gravel/ Solid block/ SSM		Sand		Remarks
				Constant	Quantity	Constant	Quantity	
1	Plain Cement Concrete of mix 1:4:8	Cum	1.97	0.89	1.76	0.47	0.92	
2	Reinforced cement concrete of design mix M25	Cum	11.53	0.70	8.07	0.47	5.42	
3	Plain Cement Concrete of mix M20 for chejja	Sqm	15.57	0.05	0.81	0.03	0.53	
4	Precast solid concrete block with CM1:4(40x20x20)	Sqm	120.63			0.02	2.41	
5	Precast solid concrete block with CM1:4(40x10x20)	Sqm	3.88			0.01	0.04	
6	15mm thick cement plaster in single coat with cement mortar 1:3	Sqm	224.59			0.01	2.92	
7	18mm thick cement plaster in single coat with cement mortar 1:4 (161.04+91.80)	Sqm	154.80			0.02	3.10	
	Total				**10.64**		**15.33**	

Material	Quantity	Rate	Amount
Size Stone	0.00	158.00	0.00
Jelly / Metal	10.64	108.00	1148.89
Sand	15.33	104.00	1594.49
		Total	2743.38

14/08.

14/8/2020